Name: Buduan, Christian Aaron C.	Date Performed: 04/12/2024
Instructor: Engr. Robin Valenzuela	Date Submitted: 04/12/2024
Section: CPE31S2	Semester and SY: 1st sem (2024-2025)

Final Exam: Hands-on Final Exam

Tools Needed:

1. VM with Ubuntu, CentOS and Ansible installed

2. Web browser


Procedure:

- 1. Create a repository and label it as "Final Exam Surname"
- 2. Clone your new repository in your VM
- 3. Create an Ansible playbook that does the following with an input of a config.yaml file and structure inventory file.
- 3.1 Install and configure one enterprise service that can be installed in Debian and Centos servers
- 3.2 Install and configure one monitoring tool that can be installed in Debian and Centos servers (if it is a stack there should be option of different host)
- 4.4 Change Motd as "Ansible Managed by <username>"
- 4. Push and commit your files in GitHub
- 5. Make sure to show evidence of input (codes) process (codes successfully running) and output (evidence of installation)
- 5. For your final exam to be counted, please paste your repository link as an answer in this exam.

Note: Extra points if you will implement the said services via containerization.

Output Screenshots:

1. Create a repository and label it as "Final Exam Surname"



2. Clone your new repository in your VM

qcacbuduan@Workstation:~\$ git clone git@github.com:buduman/Final_Exam_Buduan.git
Cloning into 'Final_Exam_Buduan'...
Warning: Permanently added the ECDSA host key for IP address '4.237.22.38' to the
 list of known hosts.
warning: You appear to have cloned an empty repository.

- 3. Create an Ansible playbook that does the following with an input of a config.yaml file and structure inventory file.
- 3.1 Install and configure one enterprise service that can be installed in Debian and Centos servers **nginx**
- 3.2 Install and configure one monitoring tool that can be installed in Debian and Centos servers (if it is a stack there should be option of different host) **nagios service**

```
qcacbuduan@Workstation:~/Final_Exam_Buduan$ cat ansible.cfg
[defaults]
inventory = inventory
remote_user = qcacbuduan
host_key_checking = True
private_key_file = ~/.ssh/ansible
deprecation_warnings=False
qcacbuduan@Workstation:~/Final_Exam_Buduan$ cat inventory
[ubuntu]
server1
[centos]
centosbuduan
```

Create config for ansible and inventory file

```
hosts: all
become: true
pre_tasks:
- name: add a MOTD
  tags: always
  lineinfile:
    path: /etc/motd
    line: "Ansible Managed by qcacbuduan"

    name: update repository index (CentOS)

  tags: always
  dnf:
    update cache: yes
  changed when: false
  when: ansible distribution == "CentOS"
- name: install updates (Ubuntu)
  tags: always
  apt:
    update cache: yes
  changed when: false
  when: ansible distribution == "Ubuntu"
hosts: ubuntu
become: true
roles:
     ubuntu
hosts: centos
become: true
roles:
     centos
```

Create config.yml file that does tasks and calls other roles to do their tasks

Under "ubuntu" role create a playbook which installs and configures nagios and nginx in Ubuntu

```
qcacbuduan@Workstation:~/Final_Exam_Buduan$ cat roles/ubuntu/tasks/main.yml
# Install Monitoring Tool in Ubuntu
- name: Install Nagios (Ubuntu)
  apt:
    name: nagios3-core
    state: latest
  when: ansible distribution == "Ubuntu"

    name: start nagios (Ubuntu)

  service:
    name: nagios3
    state: restarted
    enabled: true
  when: ansible_distribution == "Ubuntu"

    name: install nagios regs (Ubuntu)

  apt:
   name:
    - libpng-dev
    - libfreetype6-dev
    - qcc
    - libc6-dev
    - apache2
    - php
    - libgd-dev
   state: latest
  when: ansible_distribution == "Ubuntu"
```

```
name: start nagios service
  service:
    name: nagios3
    state: started
    enabled: true
  when: ansible_distribution == "Ubuntu"
# Install Enterprise service in Ubuntu
 name: install nginx
  apt:
    name: nginx
    state: latest
  when: ansible_distribution == "Ubuntu"
- name: start nginx
  service:
   name: nginx
    state: started
    enabled: true
 when: ansible distribution == "Ubuntu"
```

Under "centos" role create a playbook which installs and configures nagios and nginx in CentOS


```
qcacbuduan@Workstation:~/Final_Exam_Buduan$ cat roles/centos/tasks/main.yml
# Install Monitoring tool in CentOS


    name: Install epel repo (prereq)

 vum:
  name: epel-release
  state: latest
 when: ansible_distribution == "CentOS"
 name: install nagios (centOS)
 vum:
    name: nagios
    state: latest
 when: ansible_distribution == "CentOS"
 name: start nagios (CentOS)
 service:
    name: nagios
    state: restarted
    enabled: true
 when: ansible_distribution == "CentOS"
```


```
name: install nagios reqs (CentOS)
 yum:
   name:
   - gcc
   - glibc
   - gd-devel
   - httpd
   - php
   - freetype-devel
   - libpng-devel
   state: latest
 become: true
 when: ansible_distribution == "CentOS"
 name: start nagios service
 service:
   name: nagios
   state: started
   enabled: true
 when: ansible_distribution == "CentOS"
# Install Enterprise service in CentOS
 name: install nginx
 yum:
   name: nginx
   state: latest
 when: ansible_distribution == "CentOS"
 name: start nginx
 service:
   name: nginx
   state: started
    enabled: true
 when: ansible_distribution == "CentOS"
```

```
Run the config.yml playbook
qcacbuduan@Workstation:~/Final_Exam_Buduan$ ansible-playbook --ask-become-pass config.yml
BECOME password:
ok: [centosbuduan]
changed: [server1]
ok: [centosbuduan]
skipping: [server1]
ok: [centosbuduan]
Play progress on ubuntu "role"
ok: [server1]
ok: [server1]
changed: [server1]
TASK [ubuntu : install nagios reqs (Ubuntu)] ***********************************
ok: [server1]
ok: [server1]
ok: [server1]
```





Verifying nagios.service status on both ubuntu and CentOS servers



```
qcacbuduan@Workstation:~/Final_Exam_Buduan$ git status
On branch master
No commits yet
Untracked files:
  (use "git add <file>..." to include in what will be committed)
nothing added to commit but untracked files present (use "git add" to track)
qcacbuduan@Workstation:~/Final_Exam_Buduan$ git add -all
error: did you mean `--all` (with two dashes ?)
qcacbuduan@Workstation:~/Final_Exam_Buduan$ git add --all
qcacbuduan@Workstation:~/Final_Exam_Buduan$ git commit -m "Final_Exam_Buduan"
[master (root-commit) 1468e11] Final Exam Buduan
 5 files changed, 146 insertions(+)
create mode 100644 ansible.cfg
 CTerminahode 100644 config.yml
 create mode 100644 inventory
 create mode 100644 roles/centos/tasks/main.yml
create mode 100644 roles/ubuntu/tasks/main.yml
qcacbuduan@Workstation:~/Final_Exam_Buduan$ git push origin master
Counting objects: 12, done.
Delta compression using up to 2 threads.
Compressing objects: 100\% (7/7), done.
Writing objects: 100% (12/12), 1.47 KiB | 754.00 KiB/s, done.
Total 12 (delta 1), reused 0 (delta 0)
remote: Resolving deltas: 100% (1/1), done.
To github.com:buduman/Final_Exam_Buduan.git
   [new branch]
                     master -> master
```

Push all files into my Github repository

Github repo: https://github.com/buduman/Final Exam Buduan.git